

प्रभागीय वन अधिकारी का कार्यालय  
दक्षिण अण्डमान, विम्बर्लीगंज



**OFFICE OF THE DIVISIONAL FOREST OFFICER  
SOUTH ANDAMAN, WIMBERLYGUNJ**



No. 12-4/G-JT/Dam/Potatang/335

Date : 20.06.2017

**WORK ORDER**

Order for work described in the Schedule given to Shri P.Subramaniam, Govt. Contractor, Wimberly Gunj South Andaman to be executed as per conditions below and the rates in the Schedule of work.

**Name of Work: Renovation and Desalting of Checkweir Dam at Potatang under Jirkatang.(Full Work)**

**SCHEDULE OF WORK**

CODE	DETAIL OF WORK	Qty	UNIT	RATE	AMOUNT
2.8	Earth work in execution by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm. On plan) including dressing of sides and remaining of bathrooms lift upto 1.5m, including getting out excavated soil and disposal at surplus excavated soil as directed within a lead of 50m				
2.8.1	All kinds of soil (Foundation)	825.12	Cum	130	107265.6
NSR	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	785.925	Cum	60	47155.5