

ABSTRACT OF COST - ORIGINAL ESTIMATE

(C. P. W. D. Code Para 330-332)

Division

C. P. W. D. 13

Branch

Name of work

Sub-Division

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
15	Earthing with G.I. earth pipe 4.5 mtr long and 40 mm dia with masonry enclosure on the top etc as required.	1 set	1313	57	set	1313	57	1314.00
16	Providing and fixing earth connection from earth electrode with 4.06 (8 SWG) dia copper wire in 25 mm dia G.I. pipe from earth electrode etc as required.	15 mtr	180	80	mtr	2712	00	2712.00
17	Supplying and drawing 1/8 SWG Alumm/ copper conductor wire for loop earthing in the existing surface PVC conduit pipe along with other wires etc as required.	55 mtr	6	86	"	3773	00	3773.00
Rs.	Add @ 15% for carriage of materials from Putbay PWD store, 20 km Nallah creek. near side to work site by head load and	29,491	15	00	100	4423.65		4424.00
	by Dungi.							
19	Add @ 10% extra for working in remote tribble area.	33915	10	00	100	3391.50		3392.00

Carried over