

State And N Islands.

ABSTRACT OF COST - ORIGINAL ESTIMATE

C. P. W. D. -3

(C. P. W. D. Code Para 330-332)

Division MID

Branch Asst. Engineer B&R

Name of work Renovation & rewiring of Passenger hall at Dugong Creek Chandaman.

Sub-Division

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
1.	Wiring for light point with 1.5 sqmm pvc insulated Alum. Conductor cable in Pvc surface conduit pipe as required.							Analysis as per Analysed Rate
	Medium Point	1 NO.	306	69	each	306	69	307.00
	Long point	5 Nos.	449	00	"	2245	00	2245.00
2.	Wiring for fan point with 1.5 sqmm pvc insulated Alum. Conductor cable in Pvc surface conduit pipe if earthing the regulator etc as required							
	Medium point	1 No.	310	47	each	310	47	310.00
	Long point.	1 No.	452	20	"	452	20	452.00
3.	Wiring for 3 pin 5 A plug point with 1.5 sqmm Pvc insulated Alum. Conductor cable if providing & fixing 3 pin 5A Socket outlet on the switch board (in surface conductor conduit wiring) and 5A PE earthing in the 3rd pin etc as required.							
	Carried over							3314.00