

Central Public works Department

STATE A&N Islands. DIVISION _____ BRANCH B & R

ESTIMATE NO _____ 19 _____ - 19 _____

Note:- The entries against each item below should be made in accordance with the classification prescribed in Appendix No 4, C. P. W. D. Code

Name of works Removal and rewiring of 4 nos Type I gr (mid wife, ward attendant, engine driver and chowkider) at Duging creek.
Fund _____

Majour Head	Minor Head	Detailed head
<u>Deposits</u>	<u>for</u>	
	<u>ADINI JAN JATHI</u>	
	<u>VIKAS SAMITI, PORT BLAIR</u>	

Estimate framed by Shri. R.K. Gupta EE MID. APWD, HUL BAY Engineer
of the probable cost of Rs. 83669/= W.O. Plus Rs. 19453/= DC

Report

History:- This Preliminary comm detailed estimate amounting to Rs. 83669/= W.O. + Rs. 19453/= DC has been framed to cover the Probable cost of the above named work for obtaining A/A & E/S from the competent authority.

This existing Surface wood batten wiring which were executed long back and totally in ^{deteriorated} ~~deteriorated~~ condition. Further which were executed long back and totally in ~~deteriorated~~ condition. Further the insulation of the pvc aluminium cable also cut lived its life. Hence it is necessary to replace the existing surface wood batten wiring by ^{providing} Surface pvc conduit pipe. Hence this estimate is prepared vide letter No. 1-8/DB/EE/M/35/491 dt. 20th November 96.

Design of scope:- Provision has been made in this estimate for replacement of surface wood batten wiring with Surface pvc conduit pipe and provision made for providing fluorescent fitting and A/c ceiling fan which are totally unserviceable and the same ^{shall be} ~~shall be~~ kept in the dismantled materics account. Provision also made for carriage of materials from ^{Hul Bay Store 20 km Nallap Creek.} ~~road side~~ ^{by head} ~~and~~ ^{by dungi}. Since the buildings are located in remote trible area.