

25

ABSTRACT OF COST - ORIGINAL ESTIMATE

C. P. W. D. 3

(C. P. W. D. Code Para 330-332)

Division

Branch

Name of work

Sub-Division

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
						B/F		51,831.00
	ISA Per way i/c drilling holes on the board connection etc as required	4x1No.	357	48	each	1429	92	1430.00
15.	Earthing with G.I earth pipe 4.5 mtr long and 40mm dia with masonry enclosed on the top etc as required (Single & 2 nos Double & 1 No).	3 sets	1213	57	Set	3940	71	3940.00
16.	Providing and fixing earth connection from earth electrode with 4.06 (8 sws) dia copper wire in 25mm dia G.I. pipe from earth electrode etc as required	4x10mm	180	80	mm	7232	00	7232.00
17	Supplying and drawing 1/18 SWG (2.24mm dia Alum/copper conduit wire for loop earthing in the existing surface pvc conduit pipe along with wires etc as required.	4x20mm	6	86	"	548	80	549.00
	Carried over							64983.