

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
	Brought forward							
								B/E 11648.00
1.	Wiring for 3 pin 5A plug point with 1.5 sqmm Pvc insulated Alum. Conductor cable i/c providing & fixing 3 pin 5A socket out let on the switch board (in surface conduit wiring) and 5A P.P. Switch earthing in the 3rd pin etc as required.							
	on Board	6 Nos	138.	23	each	829.	38	829.00
	Medium point	1 No.	325.	56	"	325.	56	325.00
5.	Wiring for 3 pin 15A plug point with 4 sqmm Pvc insulated Alum. Conductor cable in surface Pvc Conduit pipe i/c providing & fixing 3 pin 15A socket out let and 15A P.P. Switch earthing in the 3rd pin etc required.							
	Long Point.	3 Nos.	579.	00	"	1737.	00	1737.00
	Total							14540.00

Sanctioned for Rupees

Engineer

Engineer