

State

ABSTRACT OF COST - ORIGINAL ESTIMATE

C. P. W. D. -3

Branch

(C. P. W. D. Code Para 330-332)

Division

Name of work

Sub-Division

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
	40mm dia with masonry enclosure on the top etc as required	1 set	1313	57	34	1313	57	40943.00
16.	Providing and fixing earth connection from earth electrode with 4.06 (8 SWG) dia copper wire in 25 mm dia G.I. pipe from earth electrode etc as required.	15 mh	180	80	mh	2712	00	2712.00
17.	Supplying and drawing 1/18 SWG (2.24 mm dia) Alum/copper Conductor wire for loop earthing in the existing Sierrace PVC conduit pipe along with other wires etc as required.	80 mh	6	86	"	548	80	549.00
18.	Add @ 15% for carriage of materials from Hubbay P.W.D. Store 20 km Nallah creek road side to work site by head land and by Dungi.	45518	15	00	100	6827	70	45518.00
19.	Add @ 10% extra for working in remote (Fible area).	52346	10	00	100	5234	60	5235.00
								57581.00
	Carried over							