

State A & N Islands.

ABSTRACT OF COST - ORIGINAL ESTIMATE

C. P. W. D. -3

(C. P. W. D. Code Para 330-332)

Division MID.Branch B & R.

Name of work

Renovation & rewiring of Police Radio bldg at Dugong Handman Sub-Division E & M.

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
1.	Wiring for light point with 1.5 sqmm Pvc insulated alum. Conductor cable in Pvc surface conduit pipe etc as required.							Analysis as per Analysis Rate
	Short Point	4 nos	178	81	each	715	24	715.00
	Medium Point	10 nos	306	69	"	3066	80	3066.00
	Long point	3 nos	449	00	"	1347	00	1347.00
2.	Wiring for fan point with 1.5 sqmm Pvc insulated alum. Conductor cable in Pvc surface conduit pipe i/c earthing the regulator etc as required.							
	Medium point.	4 nos	310	47	"	1241	88	1242.00
3.	Wiring for 3pin 5 A plug with 15 sqmm Pvc insulated alum. Conductor i/c Prdg & fixing 3pin 5A socket cut let on the Switch board in surface conduit wiring.							
								6371.00

Carried over