

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
	Brought forward							
						B/F		18716.00
	Connection etc as required	1 No.	357	48	each	357	48	357.00
12.	Earthing with G.I. earth pipe 4.5 mtr Long & 40 mm dia with 406 masonry enclosure on the top etc as required.	1 Set.	1313	57	Set	1313	57	1314.00
13.	Providing and fixing earth connection from earth electrode with 4.06 (8 sws) dia copper wire. 25 mm dia G.I. pipe from earth electrode etc as required.	10 mtr.	180	80	mtr.	1808	00	1808.00
14.	Supplying & drawing 1/8 sws Alum/copper conductor wire for loop earthing in the existing surface Pvc conduit pipe along with other wires etc as required.	30 mtr	6	86	mtr	2058	80	206.00
15.	Add @ 15% for carriage of materials from Huttbay P.O. store 20 km Nallahchakra. stands side to work ^{then} by head load & by dungi.	22401	15	00	100	3360	15	22,401.00
	Total							3360.00

Sanctioned for Rupees

Engineer

Engineer