

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
	Brought forward							
						B/F		12465.00
12.	Earthing with G.I. earth pipe 4.5 mtr long & 40 mm dia with masonry enclosure on the top etc as required.	1 set.	1313	57	set	1313	57	1314.00
13.	Providing and fixing earth connection from earth electrode with 4.06 (8 swg) dia copper wire in 25 mm dia G.I. pipe from earth electrode etc as required.	10 mtr.	180	80	mtr	1808	00	1808.00
14.	Supplying & drawing 1/8 Swg Alum/Copper conductor wire for loop earthing in the existing Surface Pvc conduit pipe along with other wires etc as required.	20 mtr.	6	86	"	137	20	137.00
15.	Add @ 15% for carriage of materials from Hubbay P.W.D. Store 20km Nallah creek road side to work site by head load ^{then} by _h bullock cart	15724.	15.	00	100	2358	60	2359.00
	demgi	14984.						
	Total							

Sanctioned for Rupees

Engineer

Engineer