

Central Public works Department

STATE AND Islands: DIVISION

BRANCH B & R

ESTIMATE NO

19

-19

Note:- The entries against each item below should be made in accordance with the classification prescribed in Appendix No 4, C. P. W. D. Conc

Name of works Renovation and rewiring of 4 nos Type I str (mid wife, ward attendant, engine driver and chowkider) at Dugong creek.

Fund

Major Head	Minor Head	Detailed head
Deposits	for	
	ADMINISTRATIVE	
	VIRUS SODALI, PART B, 101R	

Estimate framed by ... Shri. R. K. Gupta E.E. MID. PRWD, MID. BAY. Engineer
of the probable cost of Rs. 83669/- 10-0 Plus Rs. 19453/- DC.

Report

History: This preliminary and detailed estimate amounting to Rs. 83669/- 10-0 + Rs. 19453/- DC has been framed to cover the probable cost of the above named work for obtaining A/A & E/S from the competent authority.

This existing surface wood batten wiring which were executed long back and totally in ^{deteriorated} condition. Further which were executed long back and totally in deteriorated condition. Further the insulation of the pvc aluminium cable also cut lived its life. Hence it is necessary to replace the existing surface wood batten wiring by ^{providing} surface pvc conduit pipe. Hence this estimate is prepared vide letter No. 18/2B/EFM/05/491 dt. 20th November 06.

Design of scope: Provision has been made in this estimate for replacement of surface wood batten wiring with surface pvc conduit pipe and provision made for providing fluorescent lighting and the ceiling fan which are totally unserviceable and the same shall be in the dismantled material account. Provision also made for coverage of materials from road side to work site by head load and by dungi. Since the buildings are located in remote tribal area.