

Central Public works Department

STATE A & N Islands. DIVISION

BRANCH B & R

ESTIMATE NO

19

-19

Note:- The entries against each item below should be made in accordance with the classification prescribed in Appendix No 4, C. P. W. D. Code

Name of works Renovation & rewiring of Government Guest house at
Fund Bugong Creek Mandaman.

Majour Head	Minor Head	Detailed head
Deposit work	for	
	ADIM TAN JATHI	
	VIKAS SAMI	
	ROBT BLOIR	

Estimate framed by ... Shri. R.K. Gupta E.E. MID. APWD. Hub Bay. Engineer
of the probable cost of Rs. 20205/- w/o plus Rs. 4698/- de

Report

History:- The Preliminary-cum detailed estimate amounting to Rs. 20205/- w/o plus Rs 4698/- has been formed to cover the probable cost of the above named work for obtaining A/A & E/s from the competent authority.

The existing Surface wood batten wiring which were executed long back were totally in deteriorated condition. Further the insulation of the pvc aluminium conductor cable also eroded its life. Hence it is necessary to replace the existing Surface wood batten wiring by ^{providing} Surface pvc conduit pipe. Hence this estimate

Design of Scope:- Provision has been made in this estimate for replacement of wood batten wiring with Surface pvc conduit pipe and provision has been made for providing fluorescent fittings and A.C. ceiling fan which are totally unserviceable and the same kept in the dismantled materials account. Provision has been made for carriage of materials from ^{Hub Bay P.W.D. store} road side to work site by hand load and, by olungi Since the buildings is located in remote tribal area.