

Central Public Works Department

STANE AIN IslandsDIVISION M. I. DBRANCH B + R

ESTIMATE No.

199

-199

Note :- The entries against each item below should be made in accordance with the classification prescribed in Appendix No. 4, C. P. W. D. Code.

Name of works

Rewiring of 26 Nos. Onge's Huts at Sugony Creek, Little Andaman.

Fund

Majour Head	Minor Head	Detailed Head
DEPOSIT WORK	FOR A.A.J.V.S.	

Estimate framed by SRI. R. K. Gupta Executive Engineer
of the probable cost of Rs. 2,69,702/- W.O + Rs. 31,016/-

REPORT

History:- This preliminary cum detailed estimate amounting to Rs. 2,69,702/- W.O + Rs. 31,016/- D.C. has been framed to cover the probable cost of the above named work for obtaining A/A and E/s from the competent authority.

The existing surface wood batten wiring which were executed long back and totally in deteriorated condition. Further the insulation of the PVC aluminium cable also outlived its life. Hence it is necessary to replace the existing surface wood batten wiring by providing surface PVC conduit pipe. Hence this estimate is prepared vide letter no. 1-8/DB/ERM/95/491 dt. 20th Nov. 96.

Design & Scope:- Provision has been made in this estimate for replacement of surface wood batten wiring with surface PVC conduit pipe. Provision made for carriage of materials from H/May store to 20km Nallah creek & then by duff. Since the buildings are located in remote tribal area.