

133

1.	2.	3.	4.	5.	6.
					B/F 1,53,511 = 00.
13.	Providing and fixing 32A/16A SPN switch fuse unit 250W i/c drilling holes on the board, connection etc. as reqd.		26m	427-66	Ead 11119 = 00
14.	Providing and fixing 3 Way/4Way metal clad DB 250W 15A per Way i/c drilling holes on the board connection etc. as reqd.				
15.	Earthing with G.I. Earth pipe 4.5.mtr. long and 40mm dia with masonry enclosure on the top etc. as reqd.		13 sets	1313 = 57	Set 17076.00
16.	Providing and fixing earth connection from earth electrode with 4.06 (8SWG) dia copper wire in 25mm dia G.I. Pipe from earth electrode etc. as reqd.		130mb	180 = 80mb	mb 23504 = 00
17.	Supplying and drawing 2.24mm dia/1/18 SWG Alum./ Copper conductor wire for loop earthing in the existing surface VC conduit pipe alongwith other wires etc. as reqd.		260mb	6 = 86mb	mb 1784 = 00
					206994 = 00

Junior Engineer(E&M),
E & M Sub-Division,
M.I.D., Hut Bay.

Assistant Engineer,(E&M),
E&M Sub-Division,
M.I.D., Hut Bay.

Executive Engineer,
Mine Irrigation Division,
A.P.W.D., Hut Bay.

Add @ 15% for Carriage
Charges of materials from

31049 = 00

31049 = 00

Hut Bay PWD Store 20km

Nallak Creek and then by dungi = 23804 = 00

Add 10% extra for working in
remote tribal area.

= 7855 = 00

Add 3% for contingencies

Say Rs. 2,69,702/- (W.O.) + Rs. 31,016/- D.C.

Total = 2,69,702 = 00

[Signature]
J.E(E)
E & M Sub-Division

[Signature]
E & M Sub-Division
A.P.W.D. Hut Bay

[Signature]
E & M Sub-Division