

Name of work: Renovation and Rewiring of 1 No Type IV Qb at Dugong Creek, Little Andaman. (135)

1. No.	Description of work	Qty	Rate	Unit	Amount
1.	Wiring for light point with 1.5 sq. mm/3/22 PVC insulated Alum./Copper conductor cable in PVC surface conduit pipe etc. as reqd.				
	Short point	4 Nos.	178=81	Each	715=00
	Medium point	7 Nos.	306=69	Each	2147=00
	Long point	5 M.	449=00	Each	2245=00
2.	Wiring for fan point with 1.5 sq. mm/3/22 PVC insulated Alum./Copper conductor cable in PVC surface conduit pipe i/c earthing the regulator etc. as reqd.				
	Medium point	3 M.	310=47	Each	931=00
	Long point	NIL			
3.	Wiring for call bell point with 1.5 sq. mm/3/22 PVC insulated Alum./Copper conductor cable in PVC surface conduit pipe etc. as reqd.				
	Long point	1 No.	440=97	Each	441=00
4.	Wiring for 3 pin 5A plug point with 1.5 sq. mm/3/20 PVC insulated Alum./Copper conductor cable i/c pdg. & fixing 3 pin 5A socket outlet on the switch board (in surface conduit wiring) and 5A P.T. Switch, earthing in the 3rd pin etc. as reqd.				
	Short point	5 M.	138=23	Each	691=00
	Medium point	3 Nos.	325=86	Each	977=00
	Long point	NIL			
5.	Wiring for 3 pin 15A plug point with 4 sq. mm/7/20 PVC insulated Alum. conductor cable in surface PVC conduit pipe i/c pdg. & fixing 3 pin 15A socket outlet and 15A P.T. Switch, earthing the 3rd pin etc. as reqd.				
	Long point	2 M.	579=00	Each	1158=00
	Extra long point-I				9305=00
	Extra long point-II				
	Extra long point-III				