

State

ABSTRACT OF COST - ORIGINAL ESTIMATE

C.P.W.D. - 3

(C. P. W. D. Code Para 330-332)

Branch

c/o Approach foot Path cum steps, Drain, Bathing Place with over head (Sintex) Water
tanks for Torwa Ward at PHC Kalamtala, under CD-5, Rongat.

Division

Name of Work

Sub-Division

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	
①	Earth work excavation in foundation trenches or drains i/c dressings of sides and ramming of bottoms left up to 1.5m i/c getting out the excavated soil and disposed of surplus excavated soil as directed with in a lead of 50 mtr. All Kinds of soil.	90.50	65.	55	cum.	5932.	00	
②	Filling available excavated earth (consolidating rock) in trenches Plinth, sides of foundation etc in layers not exceeding 20cm depth consolidating each deposited layers by ramming and watering lead up to 50 mtr and left up to 1.50 mtr.	16.50	21.	20	cum.	350.	00	
	Carried over							