

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	
	Brought forward							
③	Supplying and filling in Plinth with local sand under floor i/c watery ramming Consolidation and dressing complete.	10.50	189.	50	cum.	1990.	00	
④	Providing and laying in Position Cement concrete of specified grade excluding the cost of carting and shuffling all waste up to Plinth level.							
(a)	1:3:6 Cement 3 sand 6 stone off 40 mm nominal size)	40.50	1392.	80	cum.	56408.	00	
(b)	1:5:10 Cement 5 sand 10 stone off 40 mm nominal size)	21.00	1137.	20	cum.	2274.	00	
	Total							

Sanctioned for Rupees.....

Engineer

Engineer