

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
	Brought forward		Rs.	P.		Rs.	P.	
(10)	12 mm thick cement plaster 1:4 (Cement 4 sand)	313.00	41.95		Sqm.	13099.	00	
(11)	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade on New Work (three or more coats)	206.00	29.85		Sqm	6149.	00	
(12)	Bonding and placing on terrace (at all floors) polythene water storage tanks of approved brand and manufacture with cover and suitable locking arrangement and making necessary holes for inlet and over flow pipe but without fitting and the base support	Total	40250.00	1.10	Rs	16400.	00	

Sanctioned for Rupees.....

Engineer

Engineer