

SCHEDULE OF QUANTITIES

ABSTRACT -C

Name of work:- Improvement of Jarawa Ward i/c Construction of C.C/R.C.C retaining
Sw:- Construction of Toilet Blocks and Improvement of Kitchen.

S.No	Items of work	Qty	Rate	Unit	Amount
1	Earth work in excavation over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed:				
a	All kinds of soil	8.00	91.50	Cum	732.00
2	Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete.	2.10	189.50	Cum	397.95
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level				
a	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	3.00	1404.70	Cum	4214.10
b	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	5.00	1549.15	Cum	7745.75
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	7.00	30.25	Cum	211.75
5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level				
a	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.30	2116.20	Cum	2751.06
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering finishing and reinforcement.				
a	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.60	2351.35	Cum	1410.81
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	1.30	2325.93	Cum	3023.71
8	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete .				
a	Thermo-Mechanically Treated bars.	363.00	21.85	Kg	7931.55