

DETAILS OF MEASUREMENTS

NAME OF WORK :- Proposed construction of Foot path and Retaining Wall near PHC Baratang.

Sl. No.	DETAILS OF WORK	NO.	MEASUREMENT			QUANTITY
			L	B	H	
1.	surface dressing			2.5		
2.	Earth Work in excavation					
	Foot Path	1X1	60.00	1.20	0.15	10.800 m ³
	P.C.C.R/Wall	1X1	25.00	1.20	$\frac{1.95+0.95}{2}$	43.500 m ³
	R.C.C.R/Wall	1X1	40.00	2.20	$\frac{3.50+1.50}{2}$	220.000 m ³
					Total	274.300 m ³
3.	sand filling					
	Foot Path	1X1	60.00	1.20	0.05	3.600 m ³
	P.C.C. Wall	1X1	25.00	1.20	0.05	1.500 m ³
	R.C.C.R/Wall	1X1	40.00	2.20	0.05	4.400 m ³
					Total	9.500 m ³
4.	providing and laying in position cement concrete					
	(1:4:8 (40mm))					
	P.C.C. Wall	1X1	25.00	1.20	0.20	6.000 m ³
	R.C.C.R/Wall	1X1	40.00	2.20	0.15	13.200 m ³
					Total	19.200 m ³