


DETAILS OF MEASUREMENTS

NAME OF WORK :-

Sl. No.	DETAILS OF WORK	NO.	MEASUREMENT			QUANTITY
			L	B	H	
9.	12mm thick Cement Plaster 1:4					
	F/path side	1X2	60.00	-	0.05	6.00 m ²
	P.C.C. Wall	1X1	25.00	-	1.00	25.00 m ²
	Top	1X1	25.00	0.25	-	6.25 m ²
	Side	1X1	25.00	-	0.05	1.25 m ²
	end	1X2	$\frac{25+40}{2}$	-	1.00	0.65 m ²
	R.C.C. Wall	1X1	40.00	-	2.00	80.00 m ²
	Top	1X1	40.00	0.20	-	8.00 m ²
	end	1X2	$\frac{20+40}{2}$	-	2.00	1.20 m ²
					Total	128.30 m ²
10.	Add. ^{67%} Cost Index on all Schedule items (except market rates)					
11.	Add. 5% Contingency charges on all Schedule items.					
12.	Add. carriage of material by mechanical Transport and head load.				2.5-	


M. K. BISWA KARMA
 Grades Supervisor
 Register No. 32/S
 Blair M.C.