

125

GOVERNMENT OF INDIA
Central Public Works Department

STATE:

DIVISION: CD-I/Port Blair

BRANCH:

ESTIMATE NO:

2011

2012

NOTE: - The entries against each item below should be made in Accordance with the classification prescribed in Appendix No: - 4, C.P.W.D Code.

Name of Work: - Construction of Sea wall behind residential area Great Andamanese of Strait Island (for a length of 500 mtr).

Major Head	Minor Head	Detailed Head
	" Deposit Work "	

This Estimate framed by, Executive Engineer, Construction Division No-I, APWD, Port Blair and Modified by Executive Engineer (Plg), CC-I, APWD, Port Blair for the probable cost of ₹.97,53,404.00 (Rupees Ninety Seven Lakhs Fifty Three Thousand Four Hundred Four Only)

Report

HISTORY: -

This revised estimate amounting to ₹.97,53,404.00 (Rupees Ninety Seven Lakhs Fifty Three Thousand Four Hundred Four Only) has been framed to cover the probable cost of the above mentioned work for obtaining revised A/A & E/S from the competent authority.

The work Construction of Sea wall behind residential area Great Andamanese of Strait Island (for a length of 500 mtr) was sanctioned during February, 2007 for an amount of ₹. 1,76,53,557/- (Rupees One Crore Seventy Six Lakhs Fifty Three Thousand Five Hundred Fifty Seven Only) The Secretary Tribal welfare during the visit to Strait Island on 07.11.2007, decided and communicated vide tour note no. 9-3/AAJVS/2007(P)/451 dated. 20th November, 2007 (Copy enclosed) construction of sea wall shall not be taken up and further communicated vide letter no. 5-2/AAJVS/2010/717 dated. 11.03.2011 (Copy enclosed) that during the meeting of Executive Council of AAJVS held on 12th August 2010 at Raj Niwas under the Chairmanship of Hon'ble Lt.Governor, it was decided that the fund provided for construction of sea wall shall be utilized for development of site.

Accordingly sea wall has not been constructed, but 02 Nos retaining wall of 3 mtr height and 16 mtr length, 03 Nos retaining wall of 02 mtr height and 25 mtr length and 01 No retaining wall of 02 mtr height and 20 mtr length has been constructed behind 06 Nos Ty-III Qtrs, 03 Nos retaining wall on sides of community hall and 01 No 02 mtr height wall constructed behind Qtr No.11 of Ty-III Qtrs. In addition to the above, a kathca approach road of 270.00 mtr length with 02 Nos RCC box culvert of 1.00 mtr x 1.00 mtr size has been constructed from guest house towards newly constructed community hall and other building sites. Extra work has also been done for terracing of newly proposed site and removal of slided earth on monsoon period. The actual expenditure deviation over A/A & E/S is beyond the permissible limits.

Hence this revised estimate.

DESIGN & SCOPE: - RCC retaining walls of approved standard design and specifications has been followed.

SPECIFICATION:- Standard C.P.W.D. specifications followed with suitable modification to suit the local site condition.

Amount : ₹.97,53,404.00
Rate : As per agreement
Method : Through Contract
Land : Available
T & P : No special T & P shall be required
WCE : Will be met out from contingencies
Time : 12 (Twelve) Months

120
15/11/11
Assistant Engineer (Plg)
Construction Circle-I
A.P.W.D., Port Blair

129
15/11/11
Executive Engineer (Plg)
Construction Circle-I
A.P.W.D., Port Blair

129
15/11/11
Superintending Engineer
Construction Circle-I
A.P.W.D., Port Blair