		Centring and shuttering including strutting, propping etc. and removal of form for a) Foundations, 199tings, bases of columns etc. for mass concrete.	Sqm 19.04	200.00 3808.00	
		b) Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	Sqm 159.95	275.00 43987.08	
ili in the second of the secon		6 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level			
		1:1:5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 nm nominal size)	Cunv 15.561	9500.00 147829,50	
		7 Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering finishing and reinforcement.			
		1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.	Cum 23.263	9600.00 223324.80	
		a) Thermo-Mechanically Treated bars.	kg 3329.894	45.00 149845.23	
		9 Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m		70.00 5922.00	
		10 Providing and fixing PVC pipe 50 mm dia for weep holes	mtr 17.750	150.00 2662.50	
		11 12 mm cement plaster of mix :	Sqm 57.30	160.00 9167.68	
		a) 1:4 (1 cement : 4 fine sand)	Sqm 57.30	644659.99	
		(Rupees Six Lakhs Forty Four Thousand Six Hundred Siz	xtu Oulu)	644660.00	
		(Rupees Six Lukus Forty Four Thousand Six Timanea Six	Lig Only)		
		ABSTR	LL ACT :- "D"	<u> </u>	
		SW:- Construction of RCC Retaining wall of 03 mtr height for a length 16 mtr at Strait Island MB No . 2436 page No, Agreement No:-80/A/EE/CD-I/PB/08-09			
		1 Earth work in excavation over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and	- Control of the cont		
		neatly dressed All kinds of soil	Cum 108.00 Cum 144.00	160.00 17280.00 120.00 17280.00	
	eng tay ang de salay ay a	2 Earth work in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift			
		upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.			
		A SALES AND A SALE	C 34 C		Page 5 of 12