

1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	8.400	15000.00	126000.00
--	-----	-------	----------	-----------

5 Centring and shuttering including strutting, propping etc. and removal of form for				
a) Foundations, footings, bases of columns etc. for mass concrete.	Sqm	146.60	250.00	36650.00
b) Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	106.00	280.00	29680.00

8 Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
a) Thermo-Mechanically Treated bars.	kg	1921.200	70.00	134484.00

11 12 mm cement plaster of mix :				
a) 1:4 (1 cement : 4 fine sand)	Sqm	44.00	190.00	8360.00

				933730.00
				18674.60
				915055.00

(Rupees Nine Lakhs Fifteen Thousand and Fifty Five Only)

ABSTRACT :- "F"

SW :- Construction of Katcha approach path.

Agreement No. 118/A/EE/CD-1/PB/2008-09

1 Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m :				
All kinds of soil	Cum	1215.00	300.00	364500.00
2 Excavation work in foundation trenches or drains not exceeding 1.5 m in width or 10 sum on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m.	Cum	30.91	280.00	8655.36
3 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level				
1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	Cum	13.84	9600.00	132864.00
1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	1.47	7600.00	11187.20
4 Centring and shuttering including strutting, propping etc. and removal of form for				
a) Foundations, footings, bases of columns etc. for mass concrete.	Sqm	29.00	260.00	7540.00