

				5	Centring and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns etc. for mass concrete.	Sqm	19.04	200.00	3808.00	
				a)	Foundations, footings, bases of columns etc. for mass concrete.					
				b)	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	159.95	275.00	43987.08	
				6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level					
				a)	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	15.561	9500.00	147829.50	
				7	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering finishing and reinforcement.					
					1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	23.263	9600.00	223324.80	
				8	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete .					
				a)	Thermo-Mechanically Treated bars.	kg	3329.894	45.00	149845.23	
				9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	Cum	84.600	70.00	5922.00	
				10	Providing and fixing PVC pipe 50 mm dia for weep holes	mtr	17.750	150.00	2662.50	
				11	12 mm cement plaster of mix :					
				a)	1:4 (1 cement : 4 fine sand)	Sqm	57.30	160.00	9167.68	
									644659.99	
									644660.00	
					(Rupees Six Lakhs Forty Four Thousand Six Hundred Sixty Only)					
				ABSTRACT :- "D"						
				SW :- Construction of RCC Retaining wall of 03 mtr height for a length 16 mtr at Strait Island MB No . 2436 page No, Agreement No:-80/A/EE/CD-1/PB/08-09						
				1	Earth work in excavation over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed	Cum	108.00	160.00	17280.00	
					All kinds of soil	Cum	144.00	120.00	17280.00	
				2	Earth work in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.					

142