

	2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming at watering, lead up to 50 m and lift upto 1.5 m	18.18	40.00	cum	727.00	
	3	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering finishing and reinforcement.					
	a)	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	14.84	7600.00	cum	112776.00	
	4	Centring and shuttering including strutting, propping etc. and removal of form for					
	a)	Foundations, footings, bases of columns etc. for mass concrete.	296.73	220.00	Sqm	65281.00	
	5	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.					
	a)	Cold twisted bars	1847.18	43.00	kg	79429.00	
	6	12 mm cement plaster of mix :					
	a)	1:4 (1 cement : 4 fine sand)	21.15	120.00	Sqm	2538.00	
	7	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth.	41.54	750.00	sqm	31155.00	
	8	Supplying and stacking of graded stone aggregate at site of size range					
	a)	90 mm to 45 mm	0.00	2350.00	Sqm	0.00	
						323038.00	
	9	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	36.00	3.00	Sqm	108.00	

202