

Add contingencies @ 5%	8587597.00	5	100	429379.85	9	200 mm thick walling consisting of Hollow cement concrete block of size 400 mm x 200 mm x 200 mm of mix 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)											
							Cum	198.806	9200.00	1829010.60	0.00	0.00	0.00	0.00			
				9146977.00													
					10	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level											
					a)	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	101.985	9900.00	1009651.50	0.00	0.00	0.00	0.00			
					11	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering finishing and reinforcement.											
					a)	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	47.520	9900.00	470448.00	0.00	0.00	0.00	0.00			
					12	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	112.865	9900.00	1117365.48	0.00	0.00	0.00	0.00			
					13	Centring and shuttering including strutting, propping etc. and removal of form for											

225