x x		100000000000000000000000000000000000000	2.3	6 Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to					
				50 m and lift upto 1.5 m	9.92	35.00	cum	347.20	
				8 Supplying and filling in plinth with Pulverized sand under floors including, watering, ramming consolidating and dressing complete.		2250.00	cum	0.00	
-			4.5	concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level	2				
	į		4.5.	3 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.00	4900.00	cum	0.00	
			4,5.	5 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	19.84	4450.00	cum	88296,90	
			4.5.	8 1:4:8 (1 Cement : 4 coarse sand : 8 graded					 = c
		-	4.1	stone aggregate 40 mm nominal size)  Providing and fixing upto floor five level	8.465	4200.00	cum	35553.00	
		2		precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc. including hoisting and setting in position with cement mortar					
			4.16	2 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	0.00	4600.00	cum	0.00	
4 4 4			5.1	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level					
			5.1.2	1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.00	4750.00	cum	0.00	
			5.1.3	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.00	3800.00	cum	0.00	
			5.14	Centring and shuttering including strutting, propping etc. and removal of form for	-0,00	3800,00	Cun	0.00	
			5.14.	Foundations, footings, bases of columns etc. for mass concrete.	132.28	90.00	sqm	11905.20	
			5.29	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.	ZVEIEV	70.00	oqiii	11703.20	
			5.29.3	Thermo-Mechanically Treated bars.	0.00	38.00	kilogram	0,00	
								138218.70	 
	-							138219.00	 
	_								