			5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level:					
			a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	14.00	3732.00	cum	52248.00	
			6	Reinforcement cement concrete work in beams, suspended floors, roofs having slope upto 15 <sup>st</sup> landing, balconies, shelves, chajjas, bands, plain, plain windows sills, staircases and spiral stair cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4(Icement :2Coarse sand: 4 graded stone aggregate 20 mm nominal size)		4092.35	cum	40923.50	
1			7	centering and shuttering including strutting, propping etc. and removal of form for					49
			(a)	Foundations, footings, bases for columns.	10.80	119.25	sqm	1287.90	
			10	Walls (any thickness) including attached pilasters, buttresses, plinth and string	·				
			b)	courses etc. Suspended floors, roofs, landings, balconies	150.00	180.40	sqm	27060.00	
			c)	and access platform.	60.00	187.35	sqm	11241.00	
			8	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.		*			
	1		a)	Thermo-Mechanically Treated bars.	7680.00	42.70	kg	327936.00	
			9	12 mm cement plaster of mix :					
			a)	1:4 (1 cement : 4 fine sand)	64.00	77.55	sqm	4963.20	
			10	6 mm cement plaster to ceiling of mix:					
			(a)	1:3(1cement :3 fine sand)	60.00	62.15	Sqm	3729.00	
							1	490389.191	
				Add cost index @ 154 %	490389.19	154.00	100.00	755199.35	
								1245588.55	
								1245589.00	
	_								
		 	ABSTRACT "B"						
		 -	Sub-	Vork;- Providing and Laying G.I	pipes				V
		 		1					F 0
		 	S.No	Providing and fixing G.I. pipes complete	UNIT	RATE	QTY	AMOUNT	
5 4 8			1	with G.I. fittings including trenching and refilling etc.  External work:	-				
-				50 mm dia. nominal bore	metre	280.10	500.00	140050.00	
			b)	80 mm dia. nominal bore	metre	458.15	450.00	206167.50	