

c)	Steel	18.69	456.00	MT	8522.64	10	Providing and fixing upto floor five level precast cement concrete hollow block walling of required thickness consisting of hollow blocks laid in cement mortar 1:6(1cement :6 sand)					
					373452.99		100 mm thick walling consisting of hollow cement concrete block of size 400mmx100mmx200mm of mix 1:3:6(1cement:3 coarse sand :6 stone aggregate 20 mm nominal size	Cum	39.93	7400.00	295482.00	
	Add contingencies @ 5%	4413496.59	5	100	220674.83		200 mm thick walling consisting of hollow cement concrete block of size 400mmx200mmx200mm of mix 1:3:6(1cement:3 coarse sand :6 stone aggregate 20 mm nominal size	Cum	131.545	6500.00	855042.50	
					4634171.00							
	(Rupees Forty Six Lakhs Thirty Four Thousand One Hundred Seventy One Only)					11	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level					
							1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	82.251	6500.00	534631.50	
	Abstract - 'B'											
	Construction of Staff Qtrs. For staff at Andamanese settlement at Strait Island. SW:- Construction of 01 No. Type-II Qtrs.(S/S)					12	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering finishing and reinforcement.					
1	Building portion as per (Arch Drg No. SA/AN/072/23/4042 Plinth area	53.71	2810.00	sqm	150925.10		1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm	Cum	36.239	7000.00	253673.00	
2	Extra for Foundation in poor soil having bearing capacity less than 10T/Sqm.	53.71	110.00	sqm	5908.10							