

	Construction of Staff Qtrs. For staff at Andamanese settlement at Strait Island. SW:- Proposed rooms for Police Personals at Strait Island (S/S)						Single rubber stopper	No	50.00	95.00	4750.00	
1	Building portion as per (Arch Drg No. SA/AN/048/208/5121 plinth area =117.90 Sqm	117.90	2810.00	sqm	331299.00	23	Providing and fixing in position facias and eaves boards with marine ply (30cm width) along with necessary fixing arrangements including nuts and bolts and drilling necessary holes etc and priming coat on unexposed surface complete.					
							19 mm thick	mtr	330.85	400.00	132340.00	
2	Extra for Foundation in poor soil having	117.90	110.00	sqm	12969.00							
3	Extra for resisting earth quake forces.	117.90	250.00	sqm	29475.00	24	Structural steel work in single section fixed without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kgs	5582.81	60.00	334968.60	
4												
4	Extra for termite proof treatment (on ground Level only).	117.90	75.00	sqm	8842.50	25	Providing and fixing ISI marked steel glazed doors, windows and ventilators of standard rolled steel sections, joints mitred and welded with 15x3mm lugs, 10cm long, embedded in cement concrete blocks 15x10x10cm of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of glass panes with glazing clips and special metal sash putty of approved make complete including applying a priming coat of approved steel primer ; excluding the cost of metal beading and other fitting as per necessary.					
5	Internal water supply & sanitary installation.	1.00	18300.00	each	18300.00		Windows-side hung	Sqm	89.40	2000.00	178804.40	
6	External service connection @ 5% on Rs. 3,31,299/-	331299.00	5.00	100	16564.95	26	Extra for providing and fixing steel beading of approved shape and section with screws instead of glazing clips and metal sash putty in steel doors, windows, ventilators and composite units.	Mtr	702.77	95.00	66763.15	
7	Internal Electrical Installation	1.00	14100.00	each	14100.00							