

d)	Cement	21.90	426.00	MT	9329.40	33	Providing and fixing hand rail by welding etc. to steel ladder railing, balcony railing & staircase railing including applying a priming coat of approved steel primer				
e)	Steel	3.11	456.00	MT	1418.16		G.I. pipes 40 mm nominal bore (class B)	Kg	669.40	135.00	90369.00
					62240.18	34	Cement concrete flooring 1:2:4 (1 40mm thick with 20mm nominal size stone aggregate	Sqm	284.28	350.00	99498.70
	Add contingencies @ 5%	1211998.90	5	100	60599.95	35	Cement plaster skirting (upto 30 cm height) with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement.				
					1272599.00		18 mm thick	Sqm	45.90	160.00	7344.00
	(Rupees Twelve Lakhs Seventy Two Thousand Five Hundred Ninety Nine Only)										
						36	Providing and fixing glass strips in joints of terrazo / cement concrete floors.				
							40 mm wide and 4 mm thick.	Mtr	136.86	25.00	3421.50
						37	Precast terrazo tiles 22mm thick with graded marble chips of size upto 12mm laid in floors, and landings, jointed with neat cement slurry mixed with pigment to match the shade of Medium shade using 50% white cement and 50% ordinary cement				0.00
						38	Precast terrazo tiles 22mm thick with graded marble chips of sizes upto 12 mm in skirting and risers of steps not exceeding 30 cm in height on 12 mm thick cement plaster 1:3 (1 cement : 3 coarse sand) jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing and polishing complete with tiles of: Medium shade using 50% white cement and 50% ordinary cement				0.00