

290

ITEM No	Item Code	SUB-HEADS AND ITEM OF WORK	QUANTITY	RATE (Rs)	UNIT	AMOUNT (Rs)
4.4	24.93	Providing and fixing UPVC moulded plain bend of required degree for UPVC soil pipes conforming to IS: 13592 type 'B' including jointing with seal ring conforming to IS: 5382 living 10mm gap for thermal expansion a) 100mm dia	24	428.19	Nos	10,277.00
		<u>SubTotal</u>				78,270.00
		<u>Total</u>				81,658.00

Add Cost Index @ 154.00 % 5,217.52

Total 86,875.52

Add Contingencies @ 5.00 % 4,343.78

Total 91,219.00

Add cess @ 1.00 % 92,131.49

Grand Total 92,131.49

Say 92,131.00

(Rupees Ninety Two Thousand One Hundred Thirty One Only)

JED
8/11/11

Executive Engineer
Construction Division No-I
APWD, Port Blair