

3.4	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete Above plinth level.					5.1
	Thermo-Mechanically Treated bars.	kg	5980.00	42.7	255346.00	5.22.6
	<u>Sub Total</u>				726654.00	
	<u>SH 4 FINISHING</u>					
4.1	12 mm cement plaster of mix :					13
4.1.1	1:4 (1 cement : 4 fine sand)	sqm	128.00	77.55	9926.4	13.1.1
	<u>Sub Total</u>				9926	
	<u>SH 5 Non Schedule Items</u>					
5.1	Carriage of Materials from Port Blair to Striat Island					
5.1.1	Cement Steel	MT	53.19	1772.6	94284.594	
5.1.2	Stone aggregate 40mm below	cum	96.62	2836.2	274033.644	
5.1.3	Stone aggregate 40mm above	cum	8.45	2816.00	23795.2	
5.1.4	Pulverised Sand	cum	54.83	2816.0	154401.28	
5.2	Providing and fixing on wall Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type as weep hole a) 75mm diameter	Mtr	14.00	129.25	1809.5	
	<u>Sub Total</u>				548325.00	

Grand Total

	1391411.00
Add Cost Index @ 154.00 %	1298352.44
Total	2689763.44
Add Contingencies @ 5.00 %	134488.172
Total	2824252.00
Add cess @ 1.00 %	28,52,494.13
Grand Total	2852494.13
Say	28,52,494/-

(Rupees twenty Eight Lakh Fifty Two Thousand Four Hundre Ninety Four Only)

Assistant Engineer(Plg),
Construction Circle No-I
APWD, Port Blair.

Executive Engineer(Plg),
Construction Circle No-I
APWD, Port Blair.

Superintending Engineer,
Construction Circle No-I
APWD, Port Blair.