


394

3.1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.					11.3
3.1.1	40mm thick with 20mm nominal size stone aggregate.	sqm	18.00	192.95	3473.1	11.3.1
	<u>Sub Total</u>				3473.1	
	SH 4 FINISHING					
4.1	12 mm cement plaster of mix :					13
4.1.1	1:4 (1 cement : 4 fine sand)	sqm	84.00	77.55	6514.2	13.1.1
	<u>Sub Total</u>				6514.2	
	SH 5 Non Schedule Items					
5.1	Carriage of Materials from Port Blair to Striat Island					
5.1.1	Cement Steel	MT	9.35	1772.6	16573.81	
5.1.2	Stone aggregate 40mm below	cum	37.30	2836.2	105790.26	
5.1.3	Stone aggregate 40mm above	cum	25.35	2816.00	71385.6	
5.1.4	Pulverised Sand	cum	19.94	2816.00	56151.04	
5.2	Providing and fixing on wall Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type as weep hole a) 75mm diamter	Mtr	16.00	129.25	2068	
	<u>Sub Total</u>				251968.71	


Grand Total

	399259.83
Add Cost Index @ 154.00 %	226828.32
Total	626088.15
Add Contingencies @ 5.00 %	31304.41
Total	657392.56
Add cess @ 1.00 %	6573.93
Grand Total	663966.49
Say	6,63,966.00

(Rupees six lakh sixty three thousand nine hundred sixty six only)


Assistant Engineer(Plg),
Construction Circle No-I
APWD, Port Blair.


Executive Engineer(Plg),
Construction Circle No-I
APWD, Port Blair.


Superintending Engineer,
Construction Circle No-I
APWD, Port Blair.