

14.43	14	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	179.00	sqm	3.20	572.80
14.45	15	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
14.45.1		a) Old work (one or more coats)	77.20	sqm	14.90	1150.28
14.54	16	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
14.54.1		a) One or more coats on old work.	26.00	sqm	22.85	594.10
14.64	17	Finishing walls with water proofing cement paint of required shade :				
14.64.1		a) Old work (one or more coats applied @ 2.20 kg/10 sum) over priming coat of primer applied @ 0.80 litrs/10 sum complete including cost of Priming coat.	106.00	sqm	27.95	2962.70
15.2	18	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge.				
15.2.1		a) 1:3:6 or richer mix	1.30	cum	368.45	478.99
15.12	19	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :				
15.12.1		a) Of area 3 sq. metres and below	5.00	each	54.60	273.00
MR	20	Providing cement concrete surface drain including earth excavation 10 cm thick base concrete and 15 cm thick with 1:3:6 (1 cement: 3 coarse sand: 6 stone aggregate 20 mm nominal size) cement concrete finished with 1:4 cement mortar (1 cement: 4 sand) cement plaster including floating coat of neat cement, inside the drain surface including disposed of surplus earth work complete. □ a) 15 x 15 cm surface drain	50.00	metre	852.50	42625.00

			Total	98204.36
Add cost index @129%	55579.36	129	100	71697.378
			Total	169901.74
Add Contingencies @ 5%	169901.74	5	100	8495.09
			Total	178396.83
Add labour cess @ 1 %	178396.83	1	100	1783.97
			Total	180180.80
			Say	180181.00

Executive Engineer
CD-I, APWD, Raichur