	Tr 2.1	Foundations, footings, bases of columns, etc. for mass concrete.	15	Sam	119.25	1788.75
	5.9.1		11	Sqm	187.35	2060.85
	5.9.3	Suspended floors, roofs, landings, balconies and access platform.	12	Sqm	162.65	1951.8
3.4	5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	14.	Sgm	238.4	3337.6
9	5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts. Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
	5.22.3	Cold twisted bars	635	. Kg	42.7	27114.5
10	11.36	Providing and fixing lst quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with				in a
		grey cement slurry @ 3.3kg per sum including pointing in white cement mixed with pigment of matching shade complete.	30	Sqm	556.6	16698
11	11.37	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in colours such as White, Ivory, Grey, Fume-Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement: 4				
		Coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	28	Sqm	598.65	16762.2
12	12.8	Providing non-asbestos high impact Polypropylene reinforced cement 6 mm thick corrugated sheets (As per IS:14871) roofing upto any pitch and fixing with polymer coated J or L hooks, bolts and nuts 8mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete excluding the cost of purlins, rafters and trusses: corrugated sheets and including cutting to size and shape wherever required.	. 8	Sqm	294.95	2359.6
13	MR	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought framed and fixed in position with:-				
9		Superior hard wood Cat-II (Kiln seasoned & chemically treated)	0.1	Cum	56956.46	5695.64
14	MR	Providing and laying hollow cement concrete blocks walling 200mm thick consisting of hollow block size 400X200X200mm of mix 1:3:6(1 cement 3 coarse sand 6 graded stone aggregate 10mm nominal and down size) laid in cement mortar 1:6(1 cement 6 coarse sand). a) Up to				Я
		floor five level.	2.7	Cum	6583.00	17774.10