

State

ABSTRACT OF COST - ORIGINAL ESTIMATE

C.P.W.D.-3

Branch

(C. P. W. D. Code Para 330-332)

Division

Name of work

Renovation of Adibasera Building at Port Blair.

Sub-Division

Item No	Sub heads and items of works	Quantity or No	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	Rs.
1.	Providing wood work in frames of false ceiling partition etc. sash and put up in position standard hard wood.	0.10	8360.00		Sqm	836.00		DER 97
2.	Providing wood work in frames of door, windows-clerestory window and other frames wrought iron and fixed in position.	0.25	13605.00		Sqm	3401.25		N/Rate
3.	Providing and fixing paneled or panelled and glazed shutters for doors and window and clerestory window i/c black painted m.s. butt hinges with necessary screws excluding paneling which will be paid for separately with old hard wood.	6.00	905.40		Sqm	5432.40		DER 97.
4.	P/F plain A C sheet ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately). 6mm thick.	6.40	195.60		Sqm	1252.00		DER 97.
5.	Cement concrete flooring 1:2:4 (1 cement 2 course sand 4 graded stone aggregate) finished with a floating coat of neat cement i/c cement slurry but excluding the cost of nosing of steps etc. complete.							
	40mm thick with 20mm nominal size stone aggregate.	5.00	100.45		Sqm	502.00		DER 97.

Carried over