

278

**ESTIMATE FOR CONSTRUCTION OF SEMI- PERMANENT
SHED AT PHOOLTALA VILLAGE:**

1	Name of office	AAJVS, Kadamtala
2	Type of shed	Semi permanent
3	Size of shed	Shed with veranda 5x3½ Mtr.
4	Justification of construction	Day and night patrolling in Phooltala village to reduce interaction between Jarawas and villagers

5. REQUIREMENT OF STORES:

Sl.No	Particular of stores	Specification	Quantity	Rate	Amount
a.	Iron wire nails	Various size	5 kgs.	70.00	350.00
b.	Nut bolts	Various size	7 kgs.	95.00	665.00
c.	Squire nail	Various size	4 kgs.	90.00	360.00
d.	G.I Sheet for roofing	8 Feet(best quality)	24 Nos.	380.00	9120.00
e.	G.I Sheet for covering three sides of shed	8 Feet (medium quality)	15 Nos.	320.00	4800.00
f.	Red oxide		10 Ltrs.	82.00	820.00
g.	Synthetic enamel paint	Sky blue	5 Ltrs.	185.00	925.00
h.	Marine plywood for door & floor	12mm	8 Nos.	1200.00	9600.00
i.	Screw	3"	3 kgs	130.00	390.00
j.	Washer		6 pkts.	27.00	162.00
k.	Has bolt (aluminum)	8mm	1No.	235.00	235.00
l.	Painting brush	3"	2 Nos.	90.00	180.00
m.	Door handle	100 mm	2 Nos.	12.00	24.00
n.	Plain sheet for roofing	18"	15 Kg	100.00	1500.00

Total: Rs. 29,131.00

6. REQUIREMENT OF MFPs:

a.	Jungle post	59 cm Girth	10 Nos.
b.	Jungle Ballies	25 cm Girth	60 Nos.
c.	Bamboo		500 Nos.

7. ROYALTY CHARGES FOR COLLECTION OF MFPs

a.	Royalty charges for collection of MFPs as mentioned items No.6 (Royalty charges for per post Rs.65/- , per bally Rs. 25/- , per 100 Nos. of bamboo Rs.25/-	2275.00
----	---	---------

8. LABOUR COMPONENTS (For collection, Fixing, Transportation & construction etc.)

a.	Collection of jungle posts i/c transportation and stacking at work site	10 Nos.	5 M/Days	205.00	1025.00
b.	Collection of J/Ballies	60 Nos.	10 M/days	205.00	2050.00