

ABSTRACT OF COST - ORIGINAL ESTIMATE (C. P. W. D. Code Para 330-332)

State

Branch

Division
 1/10 Approach foot path cum steps, Drain, Batching place with over head (sinks) water tanks for Garma Ward at PHE Kalamphala. under CD-5. Length.

Name of Work

Sub-Division

Item No.	Sub-heads and items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	
①	Earth Work excavation in foundation trenches or drains i/c drawings of sides and ramming of bottoms lift up to 1.5m i/c getting out the excavated soil and disposal of surplus excavated soil as directed with in a lead of 50mtr. All kinds of soil.	90.50	65.55		um.	59321.00		
②	filling available excavated earth (concreting grade) in trenches flush, sides of foundation etc in layers not exceeding 20cm depth consolidating each deposited layers by ramming and watering lead up to 50 mtr and lift up to 1.50 mtr.	16.50	81.80		um.	2504.00		
	Carried over							