

Item No.	Sub-heads and Items of work	Quantity or No.	Rate		Per	Amount		Total
			Rs.	P.		Rs.	P.	
	Brought forward							
(10)	12 mm thick cement plaster 1:4 (Cement 4 sand)	313.00	41.95		sqm.	13099.00		
(11)	finishing walls with water proofing coat sand of approved brand and manufacture and of required shade to give an even shade on New work (three or more coats)	206.00	29.85		sqm	6149.00		
(12)	banding and Placing on terrace (at all floors) polythene water storage tanks of approved brand and manufacture with cover and suitable leaky arrangement and making necessary holes, for water and over flow pipe but without fitting and the bare supply							
	Total	4000.00	41.10		sqm	16400.00		

Sanctioned for Rupees.....

Engineer

Engineer