

Central Public Works Department

STATE:

A & N Islands.ESTIMATE NO.DIVISION:BRANCH:

B&R

Note:- The entries against each item below should be made accordance with the classification prescribed in Appendix No.4, C.P.W.D. Code.

Name of Work:

Construction of New Nicobari Guest House at
South point Port Blair.

Fund:

Major Head

Minor Head

Detailed Head

DEPOSIT WORK

Estimate framed by.....
of the probable cost of Rs. ER. S. Venkatachalam, Surveyor of works, Consn.
Circle No. 1, APWD

Rs. 54,35,000/- (W) + Rs. 6,52,200/- (DC @ 12.00%)

REPORTR E P O R THistory:-

This preliminary estimate amounting to Rs. 54,35,000/- (W) + Rs. 6,52,200/- (DC @ 12.00%) has been framed to cover the probable cost of the above named work for according A/A and E/S from the competent authority.

Design and scope :- This estimate is prepared based on the Architectural drawing No. AN/A/²⁵⁷². The building will be ~~xxxxx~~ double storeyed RCC framed structure with C.C.H.B walling, C.C flooring. ACC/GCI sheet roofing over timber trusses. The ~~prepared~~ ^{proposed} G.Floor will be 1.50 m above the Ground level.

Following provisions have been made in this estimate (i) Construction of Building ~~xxx~~ portion. ii.) Foundation in poor soil. iii) Resisting earth quake forces. iv) Termites proof treatment. v) Development of land i/e levelling, grading, internal roads and paths on L.S basis vi) C/O ~~xxxxxx~~ a compound wall of 236 m length.