

State:

Branch:

ABSTRACT OF COST-ORIGINAL ESTIMATE
(C.P.V.D.Code, Para 330-332)

C.P.V.D-3

Division

Sub-Division

Name of Work:

Item No.	Sub-heads and Items of Works	Quantity or No.	Rate Per	Amount	Total
				5/7- 820496/00	
8.	Development of site i/e levelling, grading, internal roads and paths etc.		---	LUMP SUM --- 50,000/00	Approved vide 7-43/PE/
9.	<i>ce hallurkha compound wall</i> Construction of a compound of length 236 m of 2.1m height	236.00 m	971.00 R/M	229156/00	87/6624 dated 18.11.87.
10.	Construction of a gate of 6.00 x 2.00 m.	1 No.	---	LUMP SUM... 12,000/00	
11.	Construction of cement concrete surface				
11.	Construction of a over head water tank of capacity 8000 liters.	8000 liters.	0.65 liters	5,200/00	
12.	Construction of cement concrete surface drain of length 100 m having top width of 0.65 m and bottom clear width of 0.3 m and depth of 0.40 m.	100 m.	131.65 mtr.	13165.00	Approved vide 3-8/PE/ 1915/ dated 21-3-83.
				24750.00 (G.I. @ the rate of 188%)	

G/e 1154767/00