

निर्देश

## SPECIFICATION

DESIGN & SCOPE: This estimate has been framed based on drawing No. AN/A-2572 for Nicobar Home at South Point.


The following provision have been made in this estimate.

1. Termite proof treatment.
2. CC 1:5:10 & 1:4:8 taken Under footings & Toilet fillings respectively.
3. RBE 1:2:4 for columns beams, lintels, shelf, slabs etc.
4. Superior quality wood for doors/windows.
5. A.C sheet roofing over Tubular trusses.
6. 40 mm thick 1:2:4 floorings and 40mm thick marble chips floor.
7. Painting doors & windows, distemping for inner walls colour washing for outer wall.
8. AC Plain sheet ceiling 6mm thick.
9. Internal water supply and sanitary installations.
10. Plinth protection, CC drains, septic tank & manhole etc.

### SPECIFICATIONS:

CPWD Specifications Vol. I & II with suitable modifications to suit the local conditions shall be followed.

<u>RATE:</u>	D.S.R '1989 + 22% Cost Index.
<u>COST:</u>	Rs. 19,86,300/-
<u>W.C.E:</u>	Will be met out from the contingencies provided in the estimate.
<u>T &amp; P:</u>	No special T&P is required.
<u>METHOD:</u>	Departmentally/Contract.
<u>LAND:</u>	Shall be made available.
<u>TIME:</u>	18 Months.

  
Surveyor of Works,  
Port Blair Central Circle.

Supplied By : Saha Agency, Calcutta.