

ABSTRACT OF COST-ORIGINAL ESTIMATE.

Name of Work:- C/o Nicobarries Home at Southpoint (Phase.I).

Item No.	Sub heads and items of work.	Qty.	No.	Rate.	Per.	Amount.	Remarks.
----------	------------------------------	------	-----	-------	------	---------	----------

S.H.PRELIMINARY.

1. Preparing building site jungle clearing-dressing setting out with pegs etc.

500 Sqm 1.25 Sqm. 625

S.H.EARTH WORK.

- 2.1. Earth work on surface excavation not exceeding 1.5m in width as well as 10 Sqm on plan i/c disposal of excavated earth upto 50m and lift upto 1.5m disposed soil to be levelled and neatly dressed.

242 Cum 8.8 Cum 2130

- 2.2 Filling available excavated earth(excluding rock) in trenches,plinth,sides of foundations etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.50m.

161 Cum 5.7 Cum 918

- 2.3 Providing and injecting chemical emulsion for PRECONSTRUCTIONAL anti-termite treatment and creating a chemical barrier under and around the column pits wall trenches basement excavation,top surface of plinth filling,junction of wall and floor along the external perimeter of building expansion joints surrounding of pipes and conduits etc. complete.

328

Aldrin Emul sifiable concentrate(0.5%).

Sqm 53.5 Sqm. 17548

Contd...2/-

C/O 21221