

1.	2.	3.	4.	5.	6.	7.
----	----	----	----	----	----	----

3. S.H. CONCRETE WORK.

815 21221

- 3.1. Providing and laying cement concrete in footings and bases for columns excluding the cost of centering and shuttering 1:5:10 (1 cement, 5 coarse sand, 10 graded stone aggregate 40mm nominal size). 15 Cum 347.90 Cum 5219
- 3.2. 1:4:8 (1 cement, 4 coarse sand, 8 graded stone aggregate 40mm nominal size) 25 Cum 390.40 Cum 9760

4. S.H. REINFORCED CEMENT CONCRETE.

- 4.1. Reinforced cement concrete work in rafts footings, bases of columns etc. and mass concrete excluding the cost of centering shuttering and reinforcement 1:2:4 (1 cement, 2 coarse sand 4 graded stone aggregate 20mm nominal size) 51 Cum 573.55 Cum 29251
- 4.2. Reinforced cement concrete work in columns pillars, piers, abutments, posts and struts in all floors. - excluding the cost of centering and shuttering finishing and reinforcement 1:2:4 (1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size). 70 Cum 593.70 Cum 41559
- 4.3. Reinforced cement concrete work in lintels beams, plinth beams and bresummers in all floors excluding the cost of centering shuttering and reinforcement 1:2:4 (1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size). 77 Cum 577.60 Cum 44475

^ finishing

Contd..3/-

C/O 151485