

1.	2.	3.	4.	5.	6.	7.
4.4.	Reinforced cement concrete work in suspended floors roofs landing and balconies in all floors excluding the cost of centering shuttering finishing and reinforcement with 1;2;4(1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size).				815 151485	
4.5.	Reinforced cement concrete work in all floors i/c throating of plastered drip and moulding excluding the cost of centering shuttering finishing and reinforcement with 1;2;4(1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size).	44.4 Cum	577.6		Cum	25645
4.6.	Reinforced cement concrete work in stair cases (excluding landings) except spiral stair case preparing of the top surfaces and finishing nosing upto floor two, level but excluding the cost of centering, shuttering, finishing and reinforcement with 1;2;4 (1 Cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size).	6 Cum	608.1		Cum	3649
4.7.	Providing hoisting and fixing upto floor two level pre-cast reinforced cement concrete in shelves excluding the cost of centering, shuttering, finishing and reinforcement with 1;2;4(1 cement, 2 coarse sand, 4 graded stone aggregate 12.5mm nominal size).	1.70 Cum	620.75		Cum	1055
4.8.	Centering and shuttering i/c strutting, propping etc. and removal of form work for CC work foundation footings bases of columns etc. mass concrete and precast shelves.	1.20 Cum	877.80		Cum.	1053
4x8.	Centering and shuttering i/c strutting, propping etc. and removal of form work for CC work foundation footings bases of columns etc. mass concrete and precast shelves.	89 Sqm.	22.65		Sqm.	2016
		Cor. Id...	4/-		C/O	184903

(5)