

5

1.	2.	3.	4.	5.	6.	7.
4.9. Centering and shuttering i/c strutting propping etc. and removal of form work for RCC work foundation footings bases of columns etc. mass concrete and precast shelves.		15 Sqm	22.65	Sqm.	340	815 184903
4.10. Centering and shuttering i/c strutting, propping etc. and removal of form for RCC work columns pillars, posts and struts.		680 Sqm.	38.55	Sqm.	26214	
4.11. Centering and shuttering i/c strutting propping etc. and removal of form for lintels beams plinths beams, girders, bressumers and cantilever.		682 Sqm.	29.25	Sqm.	19949	
4.12. Centering and shuttering i/c strutting propping etc. and removal of form for suspended floors roofs landing and balconies.		429 Sqm.	47.9	Sqm.	20506	
4.13. Centering and shuttering i/c strutting propping etc. and removal of form for stairs (excluding landings) except spiral stair cases (i/c landing).		16 Sqm.	31.70	Sqm.	507	
4.14. Reinforcement for RCC work i/c bending and binding and placing in position complete cold twisted bars.	31300 Kg	kg.	9.1	kg.	284830	
5. <u>S.H. WALLING.</u>						
5.1. Hollow concrete block walling 200mm thick consisting of hollow blocks of size 200x200x400mm, laid in cement mortar 1:6 (1 cement, 6 sand).		83 Cum.	553	Cum.	45899	
5.2. Hollow concrete block walling 100mm thick consisting of hollow blocks of size 400mmx100mmx200mm, laid in cement concrete mortar						c/o: 583148
1 of mix 1:3:6 (1 cement 3 coarse sand 6 graded stone aggregate 20mm nominal size).						

Contd...5/-