

.. : 6 : -

B/S 816121

	2.	3.	4.	5.	6.	7.
		3.4 Qt.	997.85		Qt1.	3393
2. In flat. Steel work in built up tubular trusses i/c cutting hoisting fixing in position and applying a priming coat of approved steel primer welded and bolted i/c special shaped washers etc. complete.		4720 Kg	15.45		Kg.	72924
3. Providing and fixing bolts upto 300mm in length i/c nuts and washers complete.		1.7 Qt1.	1593.50		Qt1.	2709
4. Providing and fixing M.S Hand railing with horizontal M.S.Flat 25 x 3mm at tops & bottom with M.S Vertical Rod 25mm dia at 30cm C/C and bottom embedded in concrete and top welded with the M.S.Flat and 6mm dia intermediate M.S.Vertical bars at 8 cm C/C welded to the M.S. flat at top and bottom and fix 8 cm 1st class paduak top sill wrought framed and fixed in position complete.		25 Mtr.	361.8		Mtr.	9045

S.H.FLOORING.

9.1. Cement concrete flooring 1;2;4(1 cement, 2 coarse sand 4 graded stone aggregate) finished with a floating coat of neat cement i/c cement slurry, rounding of edges and strips etc. but excluding the cost of nosing of steps etc. complete.						
a. 40mm thick with 20mm nominal size stone aggregate.	393 Sqm.	43.35		Sqm.	17037	

TERAZO FLOORING.

9.2. 40mm thick marble chips flooring rubbed and polished to granolithic finish under layer 31mm						
				C/O.	921229	

Contd....9/-