

SLA and ETS recorded
by H. A. H. Gaur. A.M.
Islands

के. के. जिंदल
K. K. JINDAL
Director (C.P.W.D.)
निकोबार प्रशासन
Nadensration
पोर्ट ब्लेयर
Port Blair

C.P.W.D Code, Para - 81

GOVERNMENT OF INDIA
Central Public Works Department
P.B.N. DIVISION

ATE A-3 N Islands
ESTIMATE No.

BRANCH

10 - 19

NOTE:- The entries against each item below should be made in accordance with the classification prescribe in Appendix No. 4, C.P.W.D. Code.

Name of Works C/o Surface water tank in nicobarie3 Home at South Point
and Port Blair.

Major Head	Minor Head	Detailed Head
"4225"	VV-80'20' P. J. ST	
	VV-80'20' (1) ST	exp. 20000.00
	VV-80'20' (2) ST	exp. 20000.00
		(P.L.N.)

Estimated framed by L.R. P.K. Balachandran
of the probable cost of Rs. 2,20,165/- (Wd) + Rs. 25,319/- D.C. @ 11.50%
Executive Engineer

Report

This detailed Estimate has been amounting Rs. 2,20,165/- (Wd) + Rs. 25,319/- D.C. @ 11.50%. Thus been framed to cover the probable cost of the above named work.

The building is situated in hilly area, and the main highway is also far away from the building, so with the gravity flow of water the drain will be crisis of water often, and as this will utilized for common stay purpose of tribals, water consumption will be more. Hence this Estimate

Design & scope :- This Estimate provides for CC 1:3:6 in the walling with nominal temperature reinforcement. & Sand filling, CC flooring & 1:2:4 cover slab.

Specification :- Std - C.P.W.D specification with suitable modification to suit the site and local condition.

P.T.O.